



--- ADDENDUM #1 ---

Issued May 30, 2023 to all bidders

To be added to and made part of the Tender Documents

1.0 Intent

- .1 This addendum is issued prior to closing of bids to provide revisions to the tender documents.
- .2 Such revisions shall form part of the Tender Documents and change the original Tender Documents only in the manner and to the extent stated. **A signed copy of this addendum must be attached to the Bid and the Bidder must acknowledge receipt of this addendum in the space provided.**
- .3 The statements below are for clarification purposes in response to questions received from bidders.

2.0 Directive

- .1 Bidders are instructed to carry pricing in hydrant item #12 for tracer wire test stations (Copperhead SnakePit Model #LD14B2T-ADJ-SW) at each fire hydrant. Grounding rod to be installed at each test station location. Install both in accordance with manufacturer's installation guide and Standard Specifications. (Grounding rod standard of acceptance: Copperhead ANO-14 or approved equivalent).
- .2 Bidders are instructed to carry costs for placing, compacting, and grading embankment materials in ditch infilling applications per 01 22 00 - 53.1. Excavated road base materials to be used for this purpose to the lines and grades indicated in the drawings. All other labour and materials to construct sidewalks and carry out landscape restorations per contract items.

Kind regards,

Alexander J. de Sousa, P.Eng.
Director of Engineering & Public Works
Town of Wolfville

Representative Signature

Company

Date

-----END OF ADDENDUM #1-----