

---

## ---ADDENDUM #3---

Issued April 20, 2026 to all bidders

To be added to and made part of the Tender Documents

---

### 1.0 Intent

- .1 This addendum is issued prior to closing of bids to provide revisions to the tender documents.
- .2 Such revisions shall form part of the Tender Documents and change the original Tender Documents only in the manner and to the extent stated. **A signed copy of this addendum must be attached to the Bid and the Bidder must acknowledge receipt of this addendum in the space provided.**
- .3 The statements below are for clarification purposes in response to questions received from bidders.

### 2.0 Questions and *Responses*

- .1 Can you please provide any available data on what to expect for flow rates through the existing 300mm sanitary In Main Street?  
*There is no flow data available for this section of sanitary piping.*
- .2 The Tender form seems to have two items for 600mm x 600mm catch basins with the same quantities. Item 33.2 is for 600mm x 600mm Precast (Provisional) and 40.2 is for Yard Drain – 600mm x 600mm Precast (Provisional). Please clarify if there is supposed to be two items or just one?  
*The intention with the separate pay items is that 33.2 would cover any 600mmx600mm structures required within the roadway due to clearance restrictions to other utilities not allowing the use of 1050mm catchbasins. Item 40.2 is intended to cover any required off-street drainage.*
- .3 After visiting the site, it seems there are a few traffic signs that will need to be removed and reinstated. There is no pay item for the removal and reinstatement of these existing signs or for new signs. Can you please provide a pay item for relocating signs or new signs?  
*Removal, storage and reinstatement of existing signs to be included in 01 22 00, Part 1 – General, Item 3.*
- .4 Drawing C-003 at 0+040 shows what looks like a driveway apron but has a box drawn on the back of it. What is this?  
*The driveway apron shown is for Public Works access to a gravel parking area behind the sidewalk (depicted as rectangle). Actual requirement and location will be determined onsite with Public Works staff.*



- .5 The Drawings and Sanitary Structure table on drawing C-008 shows 6 x 1200mm SANMH and 1 1500mm SANMH but the tender form has 7 x 1050mm SANMH. Also the Storm Structure Table On C-008 shows 5 x 1200mm STMMH but the tender form shows 4 x 1050mm STMMH. Please confirm the table on the drawings is correct and change the tender form to match.

*Manhole sizing shown in the structure tables are default sizing set by Civil3D. Manholes to be provided are to be smallest diameter possible (minimum 1050mm) based on the connected pipe sizes. Based on pipe sizes, tender form is considered correct.*

*There are 5 proposed storm manholes in total. Four are covered by pay item 32.1, with the 5<sup>th</sup> (connection at Main Street) covered by pay item 36.1.*

- .6 Detail 1 on drawing C-006 shows 6m travel lane (6.74m Between Face Of Curbs) and the drawings seem to have a 6.6m travel lane (7.34m Between Face Of Curbs). Please confirm the scaled drawings are correct not the standard detail.

*The plan drawings are correct. Total asphalt surface width is 6.6m (7.34m FOC to FOC). Revise lane width on Detail 1/C-006 from 3.0m to 3.3m. Quantities in Form of Tender are correct as shown.*

Kind regards,

**Mark Fredericks**  
Senior Planner  
Town of Wolfville

---

Bidder Representative Signature

---

Bidding Company

---

Date

-----END OF ADDENDUM #3-----